



PROJECT:  
 Pierce Drive South Force Main Replacement

BIDDERS:

1  
 Pyles Plumbing  
 835 Hillcrest Industrial Blvd.  
 Macon, GA 31204

2  
 John R. Walker, Inc.  
 4038 I-475 Industrial Blvd.  
 Macon, GA 31210

CEG FILE: M0175.068

ITEM NO.	QTY.	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE
<b>1. Install MWA Furnished 6" Dips Dr 9 HDPE Force Main</b>							
a.	1	LS	Mobilization and Bonds	\$ 7,500.00	\$ 7,500.00	\$ 15,000.00	\$ 15,000.00
b.	850	LF	Install 6" HDPE Force Main by Horizontal Directional Drilling in Soil and Partially Weathered Rock. Connect to an existing 4" Cast Iron Pipe and discharging to a MWA furnished Sanitary Sewer Manhole as described on the plans.	\$ 74.00	\$ 62,900.00	\$ 116.00	\$ 98,600.00
c.	50	LF	Install 6" HDPE Force Main by Horizontal Directional Drilling in Solid Rock when a rock head is used. Measured from the point rock is encountered to the Bore Terminus. (Not the entire length of the bore.) (Used only when approved by the MWA.)	\$ 300.00	\$ 15,000.00	\$ 250.00	\$ 12,500.00
d.	1	LS	Connect to an existing 4" Cast Iron Pipe and MWA furnished Sanitary Sewer Manhole as described on the plans.	\$ 6,500.00	\$ 6,500.00	\$ 4,950.00	\$ 4,950.00
e.	1	LS	Furnish and Install Emergency Bypass Piping Complete with Protecto 401 Ceramic Epoxy Lined CI 350 Ductile Iron Pipe, Valves, Fitting, and Concrete Collar. Includes painting exposed piping.	\$ 11,700.00	\$ 11,700.00	\$ 16,940.00	\$ 16,940.00
f.	1	LS	Remove existing SSMH and install MWA furnished Sanitary Sewer Discharge Manhole. Arrange and pay for pick up and delivery of SSMH from MWA Warehouse Verify fabricated pipe openings conform to field conditions before removal of existing SSMH.	\$ 13,000.00	\$ 13,000.00	\$ 9,900.00	\$ 9,900.00
g.	1	EA	Install MWA furnished 2" Combination Air Valve in Contractor furnished Manhole.	\$ 3,500.00	\$ 3,500.00	\$ 9,450.00	\$ 9,450.00
h.	2	CY	Flowable Fill	\$ 1,500.00	\$ 3,000.00	\$ 500.00	\$ 1,000.00
<b>2. SITE WORK</b>							
a.	1	LS	Traffic Control	\$ 2,000.00	\$ 2,000.00	\$ 12,500.00	\$ 12,500.00
b.	1	LS	Utility Pavement Patching Includes Class 'A' Asphalt Patching, asphalt saw cuts, removal and disposal. This item is all inclusive for any concrete pavement, asphalt pavement and/or concrete curbing removal and replacement required to complete the force main installation.	\$ 20,000.00	\$ 20,000.00	\$ 15,895.00	\$ 15,895.00
c.	1	LF	Lift Station Access Driveway construction including grading, subgrade preparation, graded aggregate base, asphalt paving, concrete flume and rip rap outlet protection.	\$ 20,500.00	\$ 20,500.00	\$ 27,000.00	\$ 27,000.00
d.	1	LS	Establish Permanent Grassing of Disturbed Areas with Block Sod to Match Existing	\$ 10,000.00	\$ 10,000.00	\$ 12,000.00	\$ 12,000.00
<b>3. Contingency to be used at the direction of the Engineer</b>							
a.	1	LS	Contingency	\$ 10,000.00	\$ 10,000.00	\$ 10,000.00	\$ 10,000.00
				<b>BASE BID</b>	\$ 185,600.00		\$ 245,735.00

I hereby certify that this is a true and accurate Bid Tabulation of all bids received on November 9, 2023.

  
 \_\_\_\_\_  
 Don L. Carter, P.E. #18064