

BID TABULATION FOR ALL BIDS
 RECEIVED AT THE MACON WATER AUTHORITY
 ON TUESDAY, DECEMBER 9, 2025 AT 2:00 P.M.



PROJECT:

I-16 / I-75 PHASE 6 SANITARY SEWER FORCE MAIN

BIDDERS:

CEG FILE: M0175.037				1 DPC Services 42 Collins Ridge Dr. Forsyth, GA 31029		2 Pyles Plumbing & Utility Contractos, Inc. 835 Hillcrest Industrial Blvd Macon, GA 31204		3 RDJE, Inc. 679 Hwy 29 South Newnan, GA 30263		4 Helix Grading & Utility 30 Industrial Dr Zebulon, GA 30295		5 John R. Walker, Inc. 4038 I-472 Industrial Blvd Macon, GA 31210	
ITEM NO.	QTY.	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE
1. EROSION CONTROL													
a.	3300	LF	TEMPORARY SILT FENCE, TYPE C(TP 5 - SENSITIVE AREAS)	\$ 7.00	\$ 23,100.00	\$ 6.00	\$ 19,800.00	\$ 5.00	\$ 16,500.00	\$ 5.50	\$ 18,150.00	\$ 6.50	\$ 21,450.00
b.	0.9	AC.	GRASSING COMPLETE	\$ 5,800.00	\$ 5,220.00	\$ 6,000.00	\$ 5,400.00	\$ 3,900.00	\$ 3,510.00	\$ 6,000.00	\$ 5,400.00	\$ 8,500.00	\$ 7,650.00
2. SANITARY SEWER FORCE MAIN													
a.	2035	LF	SEWER FORCE MAIN - 24 INCH DIPS, DR9 HDPE, PRICE INCLUDES FURNISHING ALL EQUIPMENT, LABOR, FITTINGS AND MATERIALS TO COMPLETE THE FOLLOWING: CLEARING AND GRUBBING, INSTALLATION BY OPEN TRENCH, INSTALLTION ON EXISTING AERIAL SANITARY SEWER, BYPASS PUMPING, CONNECTION TO EXISTING 16 IN FORCE MAIN, DROP CONNECTION IN EXISTING DISCHARGE MANHOLE, TNE MEC (OR APPROVED EQUAL) COATING INSIDE DISCHARGE MANHOLE, REQUIRED TESTING & REPORTS	\$ 277.00	\$ 563,695.00	\$ 432.00	\$ 879,120.00	\$ 450.00	\$ 915,750.00	\$ 455.00	\$ 925,925.00	\$ 528.23	\$ 1,074,948.05
b.	1	EA	PLUG VALVE - 16 INCH	\$ 25,129.00	\$ 25,129.00	\$ 30,000.00	\$ 30,000.00	\$ 32,700.00	\$ 32,700.00	\$ 28,500.00	\$ 28,500.00	\$ 24,408.00	\$ 24,408.00
c.	2	EA	AIR RELEASE VALVE ASSEMBLY - 3 INCH INCLUDING DOGHOUSE MANHOLE	\$ 36,642.50	\$ 73,285.00	\$ 19,500.00	\$ 39,000.00	\$ 50,000.00	\$ 100,000.00	\$ 41,000.00	\$ 82,000.00	\$ 41,710.00	\$ 83,420.00
d.	100.0	CY	TRENCH ROCK EXCAVATION - REQUIRES VERIFICATION OF ROCK BY THE ENGINEER	\$ 175.00	\$ 17,500.00	\$ 100.00	\$ 10,000.00	\$ 110.00	\$ 11,000.00	\$ 150.00	\$ 15,000.00	\$ 95.00	\$ 9,500.00
e.	100	CY	TP II FOUNDATION BACKFILL MATERIAL (#57 STONE) - AS DIRECTED BY THE ENGINEER	\$ 80.53	\$ 8,053.00	\$ 70.00	\$ 7,000.00	\$ 80.00	\$ 8,000.00	\$ 100.00	\$ 10,000.00	\$ 65.00	\$ 6,500.00
f.	1	LS	AS BUILT SURVEY	\$ 4,500.00	\$ 4,500.00	\$ 5,000.00	\$ 5,000.00	\$ 4,525.00	\$ 4,525.00	\$ 10,500.00	\$ 10,500.00	\$ 4,950.00	\$ 4,950.00
TOTAL BASE BID (ITEMS 1A - 2F)					\$ 720,482.00		\$ 995,320.00		\$ 1,091,985.00		\$ 1,095,475.00		\$ 1,232,826.05

* multiplied by 1 not .9 showing discrepancy in final number from \$5,800 down to \$5,220
 First bid total was \$721,062 before calculation error

I hereby certify that this is a true and accurate Bid Tabulation of all bids received on December 9, 2025

Don L. Carter, P.E. #18064